
# FINAL CONSTRUCTION PLANS

CENTER GROVE H.S. WELLNESS CENTER MORGANTOWN RD. GREENWOOD, INDIANA 46143



**COUNTY LOCATION MAP** 

## FLOODPLAIN INFORMATION

00—YEAR FLOODPLAIN) AND IS NOT IN A SPECIAL FLOOD HAZARD AREA AS PLOTTED ON THE FEDERAL MERGENCY MANAGEMENT AGENCY FLOOD INSURANCE RATE MAP FOR JOHNSON COUNTY, INDIANA, COMMUNITY PANEL NO. 18081C0105D, WHICH BEARS AN EFFECTIVE DATE OF 08/02/2007.

# OWNER/DEVELOPER

CENTER GROVE COMMUNITY SCHOOL CORPORATION 3653 WEST WHITELAND ROAD PHONE: (317) 881-0515 FAX: (317) 885-4549 CONTACT: DARRELL THOMPSON EMAIL: THOMPSONJRD@CENTERGROVE.K12.IN.US

#### **ENGINEER**

CROSSROAD ENGINEERS, PC 115 N 17th AVENUE BEECH GROVE, IN 46107 PHONE: (317) 780-1555 CONTACT: GREGORY J. ILKO EMAIL: gilko@crossroadengineers.com

## **DIRECTOR**

**JOHNSON COUNTY PLANNING & ZONING 86 WEST COURT STREET** FRANKLIN, IN 46131 PHONE: (317) 346-4350 **CONTACT: MICHELE HANSARD** EMAIL: mhansard@co.johnson.in.us



**LOCATION MAP** 

#### **PLANNING ENGINEER**

JOHNSON COUNTY PLANNING & ZONING **86 WEST COURT STREET** FRANKLIN, IN 46131 PHONE: (317) 346-4350 **CONTACT: RICHARD HOOVER** EMAIL: rhoover@co.johnson.in.us

#### **COUNTY SURVEYOR**

CROSSROAD ENGINEERS, PC 86 WEST COURT STREET FRANKLIN, IN 46131 PHONE: (317) 346-4385 **CONTACT: GREGG CANTWELL** EMAIL: gcantwell@co.johnson.in.us

# SUBJECT TOPOGRAPHIC SURVEY SITE DIMENSION PLAN ENTRANCE PLAN & MAINTENANCE OF TRAFFIC GRADING PLAN DRAINAGE PLAN STORM PLAN & PROFILI SWPPP DETAILS MISCELLANEOUS DETAILS **SPECIFICATIONS** LANDSCAPE PLAN XS-1-XS-2CROSS SECTIONS

PLAN INDEX

#### **BENCHMARK INFORMATION**

SCRIRED BY COAST AND GEODETIC SURVEY 1946. 2 MI N FROM WAVERLY. IN JOHNSON COUNTY, 1.2 MILES NORTH ALONG STATE HIGHWAY 37 FROM THE ITERSECTION OF STATE HIGHWAY 144 AT WAVERLY, MORGAN COUNTY, 125 YARDS NORTH OF THE PROJECTING 7 INCHES ABOVE GROUND. PECOVERY NOTE BY IN DEPT OF NAT RES 1985 NEW DESC- AT THE INTERSECTION OF NEW STATE ROAD 144 AND OLD STATE ROAD 37, IN THE SOUTHWEST

#### LEGAL DESCRIPTION

A PART OF THE NORTHEAST QUARTER OF THE NORTHEAST QUARTER OF SECTION 16, TOWNSHIP 13 NORTH, RANG

EGINNING AT THE SOUTHEAST CORNER OF SAID QUARTER QUARTER SECTION; THENCE SOUTH 88 DEGREE: MINUTES WEST ON AND ALONG THE SOUTH LINE OF SAID QUARTER QUARTER SECTION 250.00 FEET; THENCE NORTH MINUTES EAST PARALLEL TO THE SOUTH LINE OF SAID QUARTER QUARTER SECTION 250.00 FEET TO THE EA INE OF SAID QUARTER QUARTER SECTION; THENCE SOUTH ON AND ALONG LAST SAID EAST LINE 508.00 FEET

HE PLACE OF BEGINNING, CONTAINING 2.91 ACERS MORE OR LESS.

# **TOTAL DISTURBED AREA**

2.785 acres

# UTILITIES

Note: Listed below are the Indiana Underground Plant Protection Services Contacts; Others not listed may exist

(518) 424-3950 DENNIS CRAIG


1800 W. 26TH ST MUNCIE, IN 47302 PHONE: (765) 287-2150 ` MOSTAFA KHALLAD

9209 CASTLEGATE DR INDIANAPOLIS, IN 46256 PHONE: (765) 341–1199 WAYLON HIGGINS


1000 E MAIN ST PLAINFIELD, IN 46143

WATER TOWN OF BARGERSVILLE 24 N MAIN STREET BARGERSVILLE, IN 46106


NOTE: The underground utilities shown have been located from field survey information and existing drawings. The surveyor makes no guarantees that the underground utilities comprise all such utilities in the area, either in-service or abandoned. The surveyor further does not warrant that the underground utilities shown are in the exact location indicated although the surveyor does certify that they are located as accurately as possible from information available. The surveyor has not physically located the underground utilities.





0 8 7 9 2 4 5 7 -




SHEET 200









# **UTILITIES NOTES**

CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING WITH APPLICABLE UTILITY COMPANIES FOR ALL SERVICE DIS-CONNECTS. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING TRAFFIC AND PROVIDING ALL NECESSARY FLAGMAN, BARRELS, SIGNAGE, ETC. DURING CONSTRUCTION. ALL APPLICABLE M.U.T.C.D. STANDARDS SHALL GOVERN THIS WORK. CONTRACTOR SHALL COORDINATE WITH APPLICABLE UTILITY COMPANIES AND BUILDING PLANS FOR WATER, CABLE, ELECTRIC, AND TELEPHONE CONNECTION SERVICE POINTS. CONTRACTOR TO COORDINATE WITH DUKE ENERGY FOR NECESSARY ELECTRIC SERVICE

ALL FIELD TILES DISTURBED DURING CONSTRUCTION MUST BE REPAIRED/CONNECTED NEW DRAINAGE FACILITIES. EXISTING UTILITY SIZE AND MATERIAL INFORMATION SHOWN ON THESE PLANS ARE PER THE BEST GRAPHICAL AND VISIBLE INFORMATION AVAILABLE. CONFLICTS MAY EXIST AND SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY ALL SIZING AND MATERIAL INFORMATION PROVIDED. IF ACTUAL CONDITIONS DIFFER FROM THAT INFORMATION SHOWN ON THE PLANS, THE CONTRACTOR SHALL, PRIOR TO THE INSTALLATION OF ANY PROPOSED INFRASTRUCTURE, NOTIFY THE DESIGN ENGINEER IMMEDIATELY. CONTRACTOR TO CONFIRM DOMESTIC WATER SERVICE AND METER SIZE WITH

ARCHITECTURAL PLANS PRIOR TO INSTALLATION. CONTRACTOR TO CONFIRM SIZE OF ELECTRICAL CONDUIT WITH DUKE ENERGY AND ARCHITECTURAL PLANS. CONDUIT SHALL BE INSTALLED BENEATH PAVEMENT WITH 36" SWEEPS AND PULL STRING AS NECESSARY PER DUKE ENERGY REQUIREMENTS.

STORM SEWER STRUCTURE TABLE	STORM SEWER STRUCTURE TABLE				
STR. DATA	STR. DATA				
STR. NO. 1	STR. NO. 6				
INSTALL TYPE 'B' INLET WITH NEENAH R-3287-10V CASTING OR APPROVED EQUAL AND 82 LFT OF 12"Ø RCP @ 0.31% RIM=764.56 INV OUT (12"~SE)=759.81	INSTALL TYPE 'B' INLET WITH NEENAH R-3287-10V CASTING OR APPROVED EQUAL AND 121 LFT OF 15"Ø RCP @ 0.30% RIM=762.08 INV IN (12"~NW)=759.07 INV OUT (15"~E)=759.07				
STR. NO. 2	CTD NO 7				
INSTALL TYPE 'E' INLET WITH NEENAH R-1878-A9G CASTING OR APPROVED EQUAL AND 138 LFT OF 12"Ø RCP @ 0.31% RIM=765.26 INV IN (12"~NW)=759.56 INV OUT (12"~S)=759.56	STR. NO. 7  INSTALL TYPE 'B' INLET WITH NEENAH R-3287-10V CASTING OR APPROVED EQUAL AND 44 LFT OF 18"Ø RCP @ 0.45% RIM=765.36 INV IN (15"~W)=758.71 INV IN (12"~N)=758.71 INV OUT (18"~S)=758.71				
STR. NO. 3					
INSTALL TYPE 'E' INLET WITH NEENAH R-1878-A9G CASTING OR APPROVED EQUAL AND 85 LFT OF 12"Ø RCP @ 0.50% RIM=765.38  INV IN (12"~N)=759.13  INV OUT (12"~S)=759.13  STR. NO. 4	STR. NO. 8  INSTALL TYPE 'E' INLET WITH NEENAH R-4215-C CASTING OR APPROVED EQUAL AND 81 LFT OF 18"Ø RCP @ 0.50% RIM=763.50 INV IN (18"~N)=758.51 INV OUT (18"~SW)=758.51				
	D.S. ELEV. = 758.10				
INSTALL TYPE 'B' INLET WITH	STR, NO, 11				
NEENAH R-3287-10V CASTING OR APPROVED EQUAL AND 130 LFT OF 12"Ø RCP @ 0.31% RIM=765.39 INV OUT (12"~S)=760.02	INSTALL TYPE 'E' INLET OUTLET STRUCTURE WITH NEENAH R-4215-C CASTING OR APPROVED EQUAL AND 58 LFT OF 12"Ø RCP @ 1.33% RIM=761.00				
OR APPROVED EQUAL AND 130 LFT OF 12" Ø RCP @ 0.31% RIM=765.39	INSTALL TYPE 'E' INLET OUTLET STRUCTURE WITH NEENAH R-4215-C CASTING OR APPROVED EQUAL AND 58 LFT OF 12"Ø RCP @ 1.33%				


#### STORM CULVERT DATA TABLE

#### STR. DATA CULVERT STR. NO. 9


INSTALL TWO (2) CONCRETE END SECTIONS AND 52 LFT OF 12"ø RCP @ 0.31% U.S. EL=757.66 D.S. EL.=757.50


STR. NO. 10 INSTALL TWO (2) CONCRETE END SECTIONS AND 18 LFT OF 12"ø RCP @ 2.78% U.S. EL=763.45 D.S. EL.=762.95






R   F   F   F   F   F   F   F   F   F
NO. No. 1
SHEET 400
JILLI I J J







Rim=762.08

⁻ lnv. In (12"∼NW)=759.07 - \

---Inv. Out (15"~E)=759.07----

22+00

85 LFT OF 12"ø RCP @ 0.65%

 $\int Inv. In (12"~N)=759.62$ 

Inv. Out (12"~SE)=759.62

760

755

750

22+25


755

EX. PROFILE OVER

LINE 'STM-C'

21+00

\_130 LFT OF 12"ø RCP @ 0.31%\_



EX. PROFILE OVER

Inv. In  $(15^{\circ} \sim W) = 758.71$ 

Inv. In  $(12^{\circ} \sim N) = 758.71^{-1}$ 

-Inv. Out (18"∼S)=758.71—

760

755

750

26+31


LINE 'STM-D'

121 LFT OF 15"ø RCP @ 0.30%

∱-Inv. In (12"~NW)=759.07

Inv. Out (15"~E)=759.07

25+00



SHEET

R


**KEYMAP** 

NO SCALE

<u>NOTE:</u> NO EARTHWORK DISTURBING ACTIVITY


MAY COMMENCE UNTIL A STORM WATER

MANAGEMENT PERMIT IS OBTAINED.





4Inv. Out (12"~S)=760.02

20+00




30+00






750


30+91







745

45+00







R

STORM CULVERT DATA TABLE							
STR. DATA CULVERT							
STR. NO. 9  INSTALL TWO (2) CONCRETE END SECTIONS AND 52 LFT OF 12"Ø RCP @ 0.31% U.S. EL=757.66 D.S. EL.=757.50							
STR. NO. 10  INSTALL TWO (2) CONCRETE END SECTIONS AND  18 LFT OF 12"Ø RCP @ 2.78% U.S. EL=763.45 D.S. EL.=762.95							


STORM SEWER STRUCTURE TABLE	STORM SEWER STRUCTURE TABLE				
STR. DATA	STR. DATA				
STR. NO. 1	STR. NO. 6				
INSTALL TYPE 'B' INLET WITH NEENAH R-3287-10V CASTING OR APPROVED EQUAL AND 82 LFT OF 12"Ø RCP @ 0.31% RIM=764.56 INV OUT (12"~SE)=759.81 .	INSTALL TYPE 'B' INLET WITH NEENAH R-3287-10V CASTING OR APPROVED EQUAL AND 121 LFT OF 15"Ø RCP @ 0.30% RIM=762.08 INV IN (12"~NW)=759.07 INV OUT (15"~E)=759.07				
STR. NO. 2	STR. NO. 7				
INSTALL TYPE 'E' INLET WITH NEENAH R-1878-A9G CASTING OR APPROVED EQUAL AND 138 LFT OF 12"Ø RCP @ 0.31% RIM=765.26 INV IN (12"~NW)=759.56 INV OUT (12"~S)=759.56	INSTALL TYPE 'B' INLET WITH NEENAH R-3287-10V CASTIN OR APPROVED EQUAL AND 44 LFT OF 18"Ø RCP @ 0.45; RIM=765.36 INV IN (15"~W)=758.71 INV IN (12"~N)=758.71				
STR. NO. 3	INV OUT (18"~\$)=758.71				
INSTALL TYPE 'E' INLET WITH NEENAH R-1878-A9G CASTING OR APPROVED EQUAL AND 85 LFT OF 12" Ø RCP @ 0.50% RIM=765.38 INV IN (12"~N)=759.13 INV OUT (12"~S)=759.13	STR. NO. 8  INSTALL TYPE 'E' INLET WITH NEENAH R-4215-C CASTING OR APPROVED EQUAL AND 81 LFT OF 18"Ø RCP @ 0.50% RIM=763.50 INV IN (18"~N)=758.51 INV OUT (18"~SW)=758.51				
STR. NO. 4	INV OUT (18"~SW)=758.51 D.S. ELEV. = 758.10				
INSTALL TYPE 'B' INLET WITH NEENAH R-3287-10V CASTING OR APPROVED EQUAL AND 130 LFT OF 12"Ø RCP @ 0.31% RIM=765.39 INV OUT (12"~S)=760.02	STR. NO. 11  INSTALL TYPE 'E' INLET OUTLET STRUCTURE WITH NEENAH R-4215-C CASTING OR APPROVED EQUAL AND 58 LFT OF 12"Ø RCP @ 1.33% RIM=761.00				
STR. NO. 5	INV OUT (12"~W)=755.00				
INSTALL TYPE 'B' INLET WITH NEENAH R-3287-10V CASTING OR APPROVED EQUAL AND	D.S. ELEV. = 754.23 SEE DETAIL SHEET 600 FOR ORIFICE INFORMATION				
86 LFT OF 12" Ø RCP @ 0.65% RIM=763.60					
	İ				

INV IN (12"~N)=759.62 INV OUT (12"~SE)=759.62


745

45+68

PROPOSED	LEGEND
S	PROPERTY LINE SECTION LINE PHASE LINE SETBACK LINE EASEMENT LINE FENCE LINE DITCH LINE SANITARY SEWER WITH MANHOLE SANITARY SEWER LATERAL WITH CLEANOUT STORM SEWER W/MANHOLE ELECTRIC LINE WATER LINE WATER LINE STORM MANHOLES STORM MANHOLES STORM INLETS STORM CURB INLETS AQUA—SWIRL UNITS WATER TEE 45° BEND 11.25° BEND 11.25° BEND 11.25° BEND TAPPING SLEEVE WATER VALVE FIRE HYDRANT WATER REDUCER STORTZ FDC WATER PLUG WATER VAULT ELECTRIC TRANSFORMER GENERATOR GREASE TRAP LIGHT POLE YARD LIGHT SIGN
[ <del>ZZZZZZ]</del>	LONG STORM SEWER LINE LONG SANITARY SEWER LINE



									DATE
6	8	7	9	2	4	3	2	1	NO.
		SHEE	ΞT	•	70	1			



A22 | ECP800 | B6 | ECP801 α B14 ECD801 A6 | ECP800 | A15 ECP800 A23 ECP800 B7

A16 ECP800 B2 ECD801 B10

VICINITY MAP

A vicinity map depicting the project site location is located in right half of the Erosion Control Details. PROJECT NARRATIVE

The project involves the construction of new wellness center building, parking lot, detention facility, and utility infrastructure. The project is located along Morgantown Road ±300' north of the Morgantown Road and Pennington Road intersection. Streets, curbs, parking and walks necessary for the development shall be constructed as part of the construction plans herein. A storm sewer system shall be utilized for stormwater collection. Drainage will discharge into existing ditch located soutwest corner of the site. Water, sanitary, telephone, cable, gas, and electric utilities shall serve the property as well. Construction is anticipated to begin in the fall of 2022.

LATITUDE & LONGITUDE Latitude N 39°34'27" Longitude W 86°11'51"

LEGAL DESCRIPTION

The Legal Description of the project site is located in the lower right quadrant of the Erosion Control Details. 11 BY 17 INCH PLAT

The 11x17 inch Plat has been submitted to the respective Soils and Water Conservation 100 YEAR FLOOD PLAINS, FLOODWAYS AND FLOODWAY FRINGES By graphic plotting only, this tract of land described hereon lies within Zone 'X' (areas

outside the 500—Year Floodplain) and is not in a Special Flood Hazard area as plotted on the Federal Emergency Management Agency Flood Insurance Rate Map for Johnson County, Indiana, Community Panel No. 18081C0105D, which bears an effective date of 08/02/2007. ADJACENT LAND USE

The adjacent landuses are Residential to the North, West, and South, as well as School to the East. DESCRIPTION OF TOTAL MAXIMUM DAILY LOAD (TMDL) REPORT

Location: Pollutants Addressed:

RECEIVING WATERS The receiving water for this project is Honey Creek—Turkey Pen Creek. A11 DESCRIPTION OF 303(d) LIST Name:

Location: Category: Pollutants Addressed:

A12 SOILS MAP AND DESCRIPTIONS

The soils map and all pertinent soil type information are located on the upper right quadrant of the Erosion Control Details. WETLANDS, LAKES AND WATER COURSES. There are no potential wetland areas located within the project site, nor shall any

potential wetland areas be disturbed as a result of construction A14 STATE AND/OR FEDERAL WATER QUALITY PERMITS

No State of Federal water quality permits are required for this project) EXISTING VEGETATIVE COVER The existing site is grass lawn.

EXISTING SITE TOPOGRAPHY Existing one-foot contours are shown on the Erosion Control Plan.

A17 EXISTING RUN-OFF ENTRANCE AREA

A18 EXISTING RUN-OFF DISCHARGE AREA A19 EXISTING STORMWATER SYSTEMS

The existing stormwater system sizes and dimensions are labeled on the Topographic

A20 EXISTING RETENTION/DETENTION FACILITIES A21 POTENTIAL DISCHARGES TO GROUND WATER

There are no potential locations where stormwater may enter the groundwater. TOTAL PROJECT AREA

The total project area covers  $\pm 3.348$  acres. A23 EXPECTED DISTURBED AREA

The expected project land disturbance is  $\pm 2.785$  acres. A24 PROPOSED SITE TOPOGRAPHY

Proposed one-foot contours are shown on the Erosion Control Plan. DISTURBED AREAS The construction limits (boundary of disturbed area) are shown on the Erosion Control

A26 PROPOSED STORMWATER SYSTEMS The proposed stormwater system sizes and dimensions are labeled on the Erosion Control

PROPOSED STORMWATER DISCHARGE Stormwater discharge shall leave the site via storm sewer at the southwest corner of the

Qpost Max. (10 year) = 15.30 cfs (inflow)Qpost Max. (10 year) = 3.61 cfs (outflow)A28 SITE IMPROVEMENTS

A29 SOIL STOCKPILES, BORROW/DISPOSAL AREAS

Topsoil shall be stockpiled in a convenient location (as determined by the owner and/or contractor) within the construction site as shown on the Erosion Control Plan. The shall be used as borrow areas in the event additional soil is needed for grading. A30 CONSTRUCTION SUPPORT ACTIVITIES

A31 IN-STREAM ACTIVITIES XXXXXXXXXXX.

STORMWATER POLLUTION PREVENTION - DURING CONSTRUCTION

POTENTIAL POLLUTANT SOURCES ASSOCIATED WITH CONSTRUCTION ACTIVITIES There is a potential for pollutants associated with construction machinery including diesel fuel, hydraulic fluid, engine oils and lubricants, antifreeze and other petroleum products. It is unavoidable for a small amount of these pollutants to contaminate soil in the grading and construction of the site. Sediment pollution from site disturbing activities shall be remedied by Erosion Control measures (see following sections). CONSTRUCTION ENTRANCE

The construction entrance shall be constructed at the \_\_\_\_\_ section of the project off Specifications and details are located on the Erosion Control Details. TEMPORARY & PERMANENT STABILIZATION Temporary & Permanent surface stabilization methods are shown on the Erosion Control Plan and detailed on the Erosion Control Details.

SEDIMENT CONTROL MEASURES FOR CONCENTRATED FLOW AREAS Sediment Control measures for concentrated flow areas are shown on the Erosion Control Plan. Specifications and details are located on the Erosion Control Details. SEDIMENT CONTROL MEASURES FOR SHEET FLOW AREAS Sediment Control measures for Sheet flow areas are shown on the Erosion Control Plan.

Specifications and details are located on the Erosion Control Details. RUNOFF CONTROL MEASURES Runoff control measures are shown on the Erosion Control Plan. Specifications and details

are located on the Erosion Control Details. STORMWATER OUTLET PROTECTION MEASURES Stormwater outlet protection measures are shown on the Erosion Control Plan.

Specifications and details are located on the Erosion Control Details.

GRADE STABILIZATION STRUCTURES No grade stabilization structures are required for this project. LOCĂTION, DIMENSIONS, SPECIFICATIONS AND DETAILS OF EACH STORMWATER QUALITY

Each stormwater quality measure is shown on the Erosion Control Plan and associated details/specifications are shown on the Erosion Control Details. WATERBODY QUALITY MEASURES Measures utilitized for work within waterbodies are shown on the Erosion Control Plan and

associated details/specifications are shown on the Erosion Control Details. MONITORING AND MAINTENANCE GUIDELINES Monitoring and Maintenance Guidelines are located in the middle on the Erosion Control

B12 PLANNED CONSTRUCTION GUIDLINES Planned Construction Sequence guidelines are located in the middle on the Erosion Control

B13 EROSION & SEDIMENT CONTROL MEASURES FOR INDIVIDUAL BUILDING LOTS Not applicable, as this is to be developed as

MATERIAL HANDLING AND SPILL PREVENTION Spill prevention shall be accomplished by utilizing spillguards for equipment fueling and servicing operations. Spillguards shall be 3'x3'x6" and shall be constructed of a material resistant petroleum products (including diesel fuel and oil). On—site fuel storage tanks shall have emergency storage capacity directly below the tank in case of rupture. Any hazardous material spillage shall be collected and/or cleaned immediately by a trained individual and disposed of in accordance with all federal, state and local regulations.

Indiana Department of Environmental Management Office of Emergency Response (317) 233-7745, Toll Free (800) 233-7745 \_\_ Fire Department (XXX) XXX-XXXX

\*Additional Material Handling and Spill Prevention (this sheet)\* MATERIAL HANDLING AND STORAGE Material Handling and Storage Procedure guidelines are located in the middle on the STORMWATER POLLUTION PREVENTION - POST CONSTRUCTION PROPOSED POLLUTANTS AND SOURCES ASSOCIATED WITH PROPOSED LAND USE

Potential pollutants include petroleum products and antifreeze from automobiles using the parking areas and sediment. STORMWATER QUALITY MEASURE IMPLEMENTATION

Stormwater quality measures are implemented by construction of the site improvements. PROPOSED POST CONSTRUCTION STORMWATER QUALITY MEASURES

Post construction stormwater quality measures shall consist of \_\_\_\_\_\_ detention and water quality purposes. C4 LOCATION, DIMENSIONS, SPECIFICATIONS AND DETAILS OF EACH STORMWATER QUALITY

The location of the water quality measure is at the normal pool elevation as detailed in construction plans. MAINTENANCE GUIDELINES OF POST CONSTRUCTION STORMWATER QUALITY MEASURES \_\_\_\_\_\_ shall be inspected quarterly for any plugging of the

\_\_\_ shall be cleared of any obstructions. The pond depth shall be measured annually at the center of the pond. PARTY RESPONSIBLE FOR STORMWATER POLLUTION PREVENTION

MONITORING AND MAINTENANCE GUIDELINES GRAVEL CONSTRUCTION DRIVE AND PARKING AREA:

A. Inspect weekly and after each storm event and log condition per IDEM. Inspect weekly until vegetation is established and log condition per IDEM. TEMPORARY AND PERMANENT SEEDING:

Inspect periodically, especially after storm events, until the stand is successfully established. B. Plan to add fertilizer the following growing season according to soil test

recommendations. C. Repair damaged, bare, or sparse areas by filling any gullies, re-fertilizing, over- or re-seeding, and mulchina. D. If plant cover is sparse or patchy, review the plant materials chosen, soil fertility, moisture condition, and mulching; repair the affected area either by over—seeding or by

E. If vegetation fails to grow, consider soil testing to determine acidity or nutrient deficiency problems. F. If additional fertilization is needed to get a satisfactory stand, do so according to soil test recommendations.

Reference the latest INDOT Specification. MULCHING: Inspect after storm events to check for movement of mulch or for erosion. B. If washout, breakage, or erosion is present, repair the surface, then re—seed, re—mulch,

and , if applicable, install new netting. Continue inspections until vegetation is firmly established

re—seeding and mulching after re—preparing the seed bed.

. Reference the latest INDOT Specification. EROSION CONTROL BLANKET:

A. During vegetative establishment, inspect after storm events for any erosion below the B. If any area shows erosion, pull back that portion of the blanket covering it, add soil, re-seed the area, and re-lay and staple the blanket.

After vegetative establishment, check the treated area periodically. SILT FENCE: Inspect the silt fence periodically and after each storm event.

B. If fence fabric tears, starts to decompose, or in any way becomes ineffective, replace the affected portion immediately. . Remove deposited sediment when it reaches half the height of the fence at its lowest point or is causing the fabric to bulge.

Take care to avoid undermining the fence during clean out. After the contributing drainage area has been stabilized, remove the fence and sediment deposits, bring the disturbed area to grade and stabilize. SAND BAG INLET PROTECTION:

Inspect the sandbag inlet protection periodically and after each storm event. B. Remove deposited sediment when it reaches half the height of the sandbags at the C. Remove the sandbag inlet protection and sediment deposits after contributing drainage area is stabilized.

. Inspect periodically for displaced rock material, slumping, and erosion at edges, especially downstream or downslope.

Inspect the fabric barrier after storm events, and make needed repairs immediately. B. Remove sediment from the pool area to provide storage for the next storm. Avoid damaging or undercutting the fabric during sediment removal. C. When the contributing drainage area has been stabilized, remove and properly dispose of all construction material and sediment, grade the area to the elevation of the top of

the inlet, then stabilize, SAND BAG INLET PROTECTION:

area is stabilized.

vegetation is secure.

FABRIC DROP INLET PROTECTION

. Inspect the sand bag inlet protection periodically and after each ctruly 2" storm event. B. Remove deposited sediment when it reaches half the height of the filter at the lowest

C. Remove the Sand Baq Inlet Protection and sediment deposits after contributing drainage area is stabilized. SILT SACK INLET PROTECTION

Inspect the silt sack inlet protection periodically and after each 1/2" storm even B. Remove deposited sediment when it reaches half the height of the filter at the lowest C. Remove the Silt Sack Inlet Protection and sediment deposits after contributing drainage

CONSTRUCTION SEQUENCE & SCHEDULE OF EROSION CONTROL IMPLEMENTATION

1. Silt fence and/or straw bales shall be placed around existing structures and in ditches as shown in these plans before any land disturbing activities are started. 2. Schedule a pre-construction meeting with \_\_\_\_\_ County SWCD 48 hours prior to

start of earthwork. Construct temporary gravel entrance in accordance with the "INDIANA STORM WATER QUALITY MANUAL". All other erosion control measures and detention areas shall be

installed and constructed as shown at the beginning of the project. Construct detention pond and install respective outlet structures. Strip topsoil and stockpile as shown.

Rough grade site. Disturbed areas should be seeded immediately following rough grading. Areas that will not be disturbed again should be permanently seeded. No unvegetated areas should be exposed for more than seven days.

Place drainage structures. Erosion control measures shall be placed around proposed structures as soon as they are in place and until vegetation is secure. Final grade site. All erosion control blankets shall be installed per manufacturers recommendations as soon as final grading is complete. Final paving operations. Temporary erosion control measures shall remain in place until

SENERAL EROSION CONTROL REQUIREMENTS FOR COMPLIANCE WITH IDEM GENERAL PERMIT RULES FOR STORM WATER RUNOFF FROM CONSTRUCTION SITES

All Erosion Control practices shall be in accordance with the latest edition of the INDIANA STORM WATER QUALITY MANUAL.

2. The Erosion Control measures included in this plan shall be installed prior to initial land disturbance activities or as soon as practical. Sediment shall be prevented from discharging from the project site by installing and maintaining silt fence, straw bales, sediment basins, etc. As shown on this plan, If shown on this plan, energy-dissipation devices or Erosion Control at the outfall of the storm sewer system shall be installed at the time of the construction of the outfall.

All on-site storm drain inlets shall be protected against sedimentation with silt sack inlet filters, filter fabric, or equivalent barriers as shown on this plan.

4. Except as prevented by inclement weather conditions or other circumstances beyond the control of the contractor/developer appropriate Erosion Control practices will be initiated within (7) seven days of the last land disturbing activity at the site. The site shall be stabilized by seeding, sodding, mulching, covering, or by other equivalent Erosion Control

This Erosion Control plan shall be implemented on all disturbed areas within the construction site. All measures involving Erosion Control practices shall be installed under the guidance of a qualified person experienced in Erosion Control and following the plans and specifications included herein.

6. During the period of construction activity, all sediment basins and other Erosion Control measures shall be maintained by the contractor. At the completion of construction, the contractor shall coordinate the transfer of required maintenance responsibilities with the 7. Public or private roadways shall be kept cleared of accumulated sediment. Bulk clearing

of accumulated sediment shall not include flushing the area with water. Cleared

ADDITIONAL EROSION CONTROL The contractor shall control wastes, party Bige Resolution was tewater, and other substances on the site in such a wext that the proper of states of the site by the action of winds, storm water runoff, or other forces. Proper disposal or management of all wastes and unused building materials appropriate to the nature of the waste or material is required.

sediment shall be returned to the point of likely origin or other suitable location.

9. Additional Erosion Control measures may be required by state or county agencies.

ADDITIONAL MATERIAL HANDLING AND SPILL PREVENTION PLAN

SPILL RESPONSE

water or bury.

The purpose of this plan is two fold: 1. To help protect the health and safety of those working on the site as well as the 2. Preventing the contamination of storm water runoff. Pollutants generated onsite may include gasoline, diesel fuel, oils, grease, paints, pesticides, nutrients, concrete washout, soil, solvents, paper, plastic, Styrofoam, metals, glass and other forms of liquid or solid This plan outlines procedures to help prevent health and safety issues, contamination of

storm water by onsite pollutants, help prevent fuel and chemical spills and provide a response procedure should a spill occur. PREVENTION AND READINESS

1. The contractor or responsible party will prepare a contact list in the event of a spill on the site. The contact list will have names and contact numbers. The contact list will specify first responders and a chain of command. Include information on what rcumstances require the initiation of the contact list and chain of command. 2. The contractor/owner shall maintain a list of qualified contractors, Vac—trucks, tank pumpers and other equipment or businesses auglified to do clean-up operations. Absorbent materials and supplies need to be available onsite in sufficient quantities to address minor spills. All employees need to be educated on the proper application of the absorbent materials.

3. All maintenance and equipment operators must be aware and trained for prevention of spills. A continuing education program is required for new employees and emphasizing the importance to all employees 4. All materials used in the course of a cleanup will be disposed in a manor approved by Indiana Department of Environmental Management. 5. Using water to flush spilled material will not be permitted unless authorized by a state, federal, or local agency. Tarps can be used to cover spilled material during rain events.

Minor - Small spills that typically involve oil gasoline, paint, hydraulic fluid etc. Minor spills can be controlled by the first responder at the discovery of the spill. • Contain spill to prevent material from entering storm or ground water. Do not flush with water or burv. • Use absorbent material to clean-up spill material and any subsequently contaminated soil and dispose of

Semi-significant Spills - Approximately ten gallons or less of pollutant with no contamination of ground or surface waters. Minor spills can be generally controlled by the first responder with help from other site personnel. This response may require other operations to stop to make sure the spill is quickly and safely addressed. At the discovery of the spill: • Contain spill to prevent material from entering storm or ground water. Do not flush with

• Use absorbent material to clean—up spills and dispose of properly. Spills on impervious surfaces should be contained with a dry absorbent. Spills on clavey soils should be contained by constructing an earthen dike and should be disposed of as soon as possible to prevent migration deeper into the soil and groundwater. Dispose of contaminated soils or absorbents properly. Contact 911 if this spill could be a safety issue.

 Contact supervisors and designated inspectors immediately • Contaminated solids to be removed to an approved landfill.

Major or Hazardous Spills - More than ten gallons, there is the potential for death, injury or illness to humans or animals or has the potential for surface or groundwater pollution • Control or contain the spill without risking bodily harm. Temporarily plug storm drains if possible to prevent migration of the spill into the stormwater system. • Immediately contact the local Fire Department at 911 to report any hazard material

• Contact supervisors and designated inspectors immediately. Other county or municipal officials (list as needed) responsible for storm water facilities should be contacted as well. The contractor is responsible for having these contact numbers available at the job site. A written report should be submitted to the owner as soon as possible. • As soon as possible but within 2 hours of discovery, contact the Department of

Environmental Management. Office of Emergency Response 1-888-233-7745. The following information should be noted for future reports to IDEM or the National Response Center.

o Name, address and phone number of person making the spill report o The location of the spill o The time of the spill

o Identification of the spilled substance o Approximate quantity of the substance that has been spilled or may be further spilled

o The duration and source of the spill o Name and location of the damaged waters o Name of spill response organization o What measures were taken in the spill response

o Other information that may be significant Additional regulation or requirements may be present. A spill response professional should be consulted to make sure all appropriate and required steps have been taken. Contaminated solids should only be removed from the site after approval is given by

THE FOLLOWING PROCEDURES AND PRACTICES WILL HELP PREVENT UNNECESSARY SPILLS

I. Vehicle and Equipment Fueling

Description and Purpose: • Vehicle equipment fueling procedures and practices are designed to prevent fuel spills and leaks, and reduce or eliminate contamination of stormwater. This can be accomplished by using offsite facilities, fueling in designated areas only, enclosing or covering stored fuel, implementing spill controls, and training employees and subcontractors in proper fueling procedures.

• Onsite vehicle and equipment fueling should only be used where it is impractical to send vehicles and equipment offsite for fueling.

• Use offsite fueling stations as much as possible. These businesses are better equipped to handle fuel and spills properly. Performing this work offsite can also be economical by eliminating the need for a separate fueling area at a site. • Discourage "topping-off" of fuel tanks.

 Absorbent spill cleanup materials and spill kits should be available in fueling areas and on fueling trucks, and should be disposed of properly after use. • Drip pans or absorbent pads should be used during vehicle and equipment fueling, unless the fueling is performed over an impermeable surface in a dedicated fueling area. • Use absorbent materials on small spills. Do not hose down or bury the spill. Remove the absorbent materials promptly and dispose of properly. • Avoid mobile fueling of mobile construction equipment around the site; rather, transport

the equipment to designated fueling areas. • Train employees and subcontractors in proper fueling and cleanup procedures. • Dedicated fueling areas should be protected from stormwater run-on and runoff, and should be located at least 50 feet away from the downstream drainage facilities and watercourses. Fueling must be performed on level—grade areas. • Protect fueling areas with berms and dikes to prevent run—on, runoff, and to contain

• Nozzles used in vehicle and equipment fueling should be equipped with an automatic shutoff to control drips. Fueling operations should not be left unattended. • Federal, state, and local requirements should be observed for any stationary above ground storage tanks.

Inspection and Maintenance • Vehicles and equipment should be inspected each day of use for leaks. Leaks should be repaired immediately or problem vehicles or equipment should be removed from the project site. Keep ample supplies of spill cleanup materials onsite.

• Immediately clean up spills and properly dispose of contaminated soils. <u>II. Solid Waste Management</u>

• Solid waste management procedures and practices are designed to prevent or reduce the discharge of pollutants to stormwater from solid or construction waste by providing designated waste collection areas and containers, arranging for regular disposal, and training employees and subcontractors.

Suitable Applications: This BMP is suitable for construction sites where the following wastes are generated or

• Solid waste generated from trees and shrubs removed during land clearing, demolition of existing structures (rubble), and building construction.

• Packaging materials including wood, paper, and plastic.

transport and package construction materials.

• Scrap or surplus building materials including scrap metals, rubber, plastic, glass pieces, and masonry products. Domestic wastes including food containers such as beverage cans, coffee cups, paper bags, plastic wrappers, and cigarettes, • Construction waste including brick, mortar, timber, steel and metal scraps, pipe and electrical cuttings, non—hazardous equipment parts. Styrofoam and other materials send ne following steps will help keep a clean site and reduce stormwater pollution:

• Select designated waste collection areas onsite. • Inform trash—hauling contractors that you will accept only watertight dumpsters for

onsite use. • Inspect dumpsters for leaks and repair any dumpster that is not watertight. Provide an adequate number of containers with lids or covers that can be placed over the container to keep rain out or to prevent loss of wastes when it is windy.

• Plan for additional containers and more frequent pickup during the demolition phase of construction. • Collect site trash daily, especially during rainy and windy conditions.

• Remove this solid waste promptly since erosion and sediment control devices tend to collect litter. Make sure that toxic liquid wastes (used oils, solvents, and paints) and chemicals (acid, pesticides, additives, curing compounds) are not disposed of in dumpsters designed for construction debris.

• Do not hose out dumpsters on the construction site. Leave dumpster cleaning to the trash hauling contractor. Arrange for regular waste collection before containers overflow. Clean up immediately if a container does spill.

authorized disposal areas. Solid waste storage areas should be located in areas prone to flooding or ponding. • Locate solid waste dumpster a minimum of 50' away from storm water inlets or other drainage facilities. • Locate dumpster on stone or earth to minimize the potential for spills or leaks to drain

• Make sure that construction waste is collected, removed, and disposed of only at

Inspection and Maintenance: • Inspect and verify that activity—based BMPs are in place prior to the commencement of associated activities. While activities associated with the BMP are under way, inspect weekly to verify continued BMP implementation. Inspect BMPs subject to non-stormwater discharge daily while non-stormwater

discharges occur. • Inspect construction waste are regularly. Arrange for regular waste collection.

immediately into a drainage facility.

III. Concrete Washout

The following steps will help reduce stormwater pollution from concrete wastes: • Discuss the concrete management techniques described in the BMP (such as handling of concrete waste and washout) with the reddy-mix concrete supplier before any deliveries are made.

subcontractors' agreements. • Store dry and wet materials under cover, away from drainage areas. Avoid mixing excess amounts of fresh concrete. Perform washout of concrete trucks offsite or in designed areas only.

 Do not wash concrete trucks into storm drains open ditches streets or streams. • Do no allow excess concrete to be dumped onsite, except in designed areas. For onsite washout: • Locate washout areas at least 50 feet from storm drains, open ditches, or water

• Incorporate requirements for concrete waste management into material supplier and

• Do not allow runoff from this area by constructing a temporary pit or bermed area large enough for liquid and solid waste. • Wash out wastes into the temporary pit where the concrete can set, be broken up, and then disposed properly. Avoid creating runoff by drinking water to a bermed or level area when washing concrete to remove fine particles and expose the agareagte. • Do not wash sweepings form exposed aggregate concrete into the street or storm drain.

Purpose— To prevent spills during the normal maintenance of construction machinery.

Collect and return sweepings to aggregate base stockpile or dispose in the trash.

Implementation— Where and when feasible, maintenance shall be preformed offsite in covered facility with an impervious floor.

 Use a dedicated site for machinery maintenance • Site the maintenance area at least 50 feet from storm water inlets or water bodies • Maintain clean up materials close at hand. Utilize drip pans and absorbent pads to prevent oils from reaching the soil surface. · Inspect equipment daily for leaks or worn hoses. Repair or replace to prevent onsite

V. Fluids, paints, solvents and other chemicals storage and use

Purpose— To prevent spills during the use and storage of the materials

Properly dispose of all fluids removed or spilled from machinery.

Implementation-• Store materials in there original containers

prevent additional sedimentation.

protected to prevent soil erosion.

ANCHORING METHODS

SET STRAIGHT)

MULCH ANCHORING TOOL OR FARM

CLEATING WITH DOZER TRACKS

WOOD HYDROMULCH FIBERS

NETTING (SYNTHETIC OR BIO-

DEGRADABLE MATERIAL)

SOIL STABILIZERS

SYNTHETIC TACKIFIERS, BINDERS, OR

DISK (DULL, SERRATED, AND BLADES

 Maintain safety data sheets on all products Store materials in a weather proof/vandal resistant locker or building Keep materials away from flammable sources

• Provide and read instructions for the proper use and storage of all materials • For bulk material stored onsite, provide diking or double containment in case of leaks or • No washout of solvent from paint supplies should be done near or into a storm water inlet or other drainage facility. <u>. Disposal of sediment laden water</u>

Purpose— To prevent the purposeful discharge of sediment laden water into waters of the • The sediment and any other pollutant from all pumping or dewatering operations that

discharge into storm sewers, wetlands, drainage ways or water bodies must be removed from the water before it's discharged. • A suitable practice is needed at the discharge to allow the suspended solids to be removed from the water column. Slow moving water and time are needed components for an effective practice. Mechanical filters and chemical flocculants can do an excellent job of removing the fine materials.

erosion resistant surfaces. The outlet of the pumping bag must be erosion resistant to

• Pumping operations that are moving clean water through a site are not required to

have a pumping bag or similar device at the outlet. The point of discharge should be

MULCH ANCHORING METHODS

APPLICATION METHOD

DOZER CLEATS.

RECOMMENDATIONS.

SHOULD BE FOLLOWED.

CRIMP OR PUNCH THE STRAW OR HAY

OPERATE MACHINERY ON THE CONTOUR

OPERATE DOZER UP AND DOWN SLOPE

TO PREVENT FORMATION OF RILLS BY

APPLY ACCORDING TO MANUFACTURER'S

APPLY ACCORDING TO MANUFACTURER'S

INSTALL NETTING IMMEDIATELY AFTER

APPLYING MULCH. ANCHOR NETTING

WITH STAPLES. EDGES OF NETTING

STRIPS SHOULD OVERLAP WITH EACH

UP-SLOPE STRIP OVERLAPPING FOUR

TO SIX INCHES OVER THE ADJACENT

DOWN-SLOPE STRIP. BEST SUITED TO

SLOPE APPLICATIONS. IN MOST INSTANCES,

INSTALLATION DETAILS ARE SITE SPECIFIC

SO MANUFACTURER'S RECOMMENDATIONS

TWO TO FOUR INCHES INTO THE SOIL.

ANNUAL RYEGRASS 1.0 LBS. 40 LBS. COVER SEED 1 DEEP \* \* NOT NECESSARY WHERE MULCH IS APPLIED. Sediment removal pumping bags may be used at the outlet of a pump. The bags must be sized appropriately for the amount of flow. The practice needs to be installed on



NOT TO SCALE

Johnson County, Indiana (IN081) CROSBY URBAN LAND-MIAMI SILT LOAM COMPLEX, eroded (YcmB2) This slightly sloping soil is in recessionial, ground, and water-lain moraines. Slopes are 2 to 4 percent. Runoff is medium. Soil of this type is typically

somewhat poorly drained, but has no frequency of ponding or flooding.


MIAMI SILT LOAM URBAN LAND COMPLEX, eroded (YmsB2) This slightly sloping soil is found in the till plains of loess over loamy till soils. Slopes are 2 to 6 percent. Runoff is high. Soil of this type is typically moderately well drained with no frequency of flooding or ponding.


BROOKSTON SILTY CLAY LOAM-URBAN LAND COMPLEX (YbvA) This nearly level soil is found in depressions of till plains. Slopes are 0 to 2 percent. Runoff is negligible. Soil of this type is typically poorly drained with no frequency of flooding but is known for frequently ponding.


LEGAL DESCRIPTION

PART OF THE NORTHEAST QUARTER OF THE NORTHEAST QUARTER OF SECTION 16, TOWNSHIP 13 NORTH, RANGE

3 EAST OF THE SECOND PRINCIPAL MERIDIAN, DESCRIBED AS FOLLOWS: BEGINNING AT THE SOUTHEAST CORNER OF SAID QUARTER QUARTER SECTION; THENCE SOUTH 88 DEGREES 2-MINUTES WEST ON AND ALONG THE SOUTH LINE OF SAID QUARTER QUARTER SECTION 250.00 FEET; THENCE NORTH PARALLEL TO THE EAST LINE OF SAID QUARTER QUARTER SECTION 508.00 FEET: THENCE NORTH 88 DEGREES 24 MINUTES EAST PARALLEL TO THE SOUTH LINE OF SAID QUARTER QUARTER SECTION 250.00 FEET TO THE EA LINE OF SAID QUARTER QUARTER SECTION; THENCE SOUTH ON AND ALONG LAST SAID EAST LINE 508.00 FEET T THE PLACE OF BEGINNING, CONTAINING 2.91 ACERS MORE OR LESS.







TEMPORARY SEEDING DATES

IAN |FEB |MAR|APR |MAY|JUN |JUL |AUG|SEP |OCT |NOV |DE

WHEAT OR RYE

SPRING OATS

DORMANT SEEDING \*\*

CREEPING RED FESCUE FESTUCA RUBRA

KENTUCKY BLUEGRASS

TALL FESCUE FESTUCA L ARUNDINACEA

PERENNIAL RYEGRASS

LOLIUM PERENNE

CORANILLA VARIA

TRIFOLIUM PRATENSE

GOOD MEDIUM

CONSIDERING BEST SEEDING DATES.

CROWNVETCH

POA PROTINSIS

\*\* HNCREASE SEEDING APPLICATION BY 50%.

TEMPORARY SEEDINGS

TALL FESCUE | 170 | 4 | 5.5 - 8.3 | 1-PREFERRED 2-WILL TOLERATE \*\* - INOCULATE WITH SPECIFIC INOCULATES

MFD. 1 | 20-25 | 12-18 | 7-21

MED. 1 | 25-35 | 12-18 | 10-20


|LOW| 1 |24-35|24-36|5-14|

MED- 2 15-20 12-18 5-10

|LOW| 1 | 5-10 | 24 | 14-21


SALT TOLERANCE (TO BOTH SOIL SALTS AND SPRAY)

| MED. | 1 | 7-10 | 18 | 5-10 | S | S



WHITELAN

BARGERSVILLE




STAPLE PATTERN DETAIL

SEEDBED PREPARATION APPLY LIME TO RAISE THE pH TO THE LEVEL NEEDED FOR SPECIES BEING SEEDED. APPLY 23 LBS. OF 12-12-12 ANALYSIS FERTILIZER (OR EQUIVALENT) PER 1,000 SQ. FT. (APPROXIMATELY 1,000 LBS. PER ACRÈ) OR FERTILIZE ACCORDING TO TEST, APPLICATION OF 150 LBS, OF AMMONIUM NITRATE ON AREAS LOW IN ORGANIC MATTER AND FERTILITY WILL GREATLY ENHANCE VEGETATIVE GROWTH. WORK THE FERTILIZER AND LIME INTO THE SOIL A DEPTH OF 2 TO 3 INCHES WITH A HARROW, DISK, OR RAKE OPERATED ACROSS THE SLOPE AS MUCH AS


TOLERANCE


IT - MEDIUM TOLERANCE


FERTILIZER AND LIME SHALL MEET REQUIREMENTS OF INDOT STANDARD SPECIFICATIONS 1995. SELECT A SEED MIXTURE BASED ON PROJECTED USE OF THE AREA WHILE





JOHNSON COUNTY














APPROVED FEBRUARY 27, 2018

REV DATE: OCT 2016







TOWN OF BARGERSVILLE, INDIANA

#### . SCOPE OF WORK

- A. EXTENT: THE WORK REQUIRED UNDER THIS SECTION CONSISTS OF ALL EXCAVATING, FILLING, ROUGH GRADING AND RELATED ITEMS NECESSARY TO COMPLETE THE WORK INDICATED ON THE DRAWINGS AND DESCRIBED IN THE SPECIFICATIONS. THE CONTRACTOR SHALL NOTIFY IN WRITING THE OWNER AND THE ENGINEER OF ANY CHANGES, ERRORS OR OMISSIONS FOUND ON THE PLANS OR IN THE FIELD, BEFORE WORK IS STARTED OR RESUMED.
- 1. IN GENERAL, THE ITEMS OF WORK TO BE PERFORMED UNDER THIS SECTION SHALL INCLUDE CLEARING AND GRUBBING, REMOVAL OF TREES AND STUMPS, STRIPPING AND STORAGE OF TOPSOIL, 6. ROLLING FILL COMPACTION AND ROUGH GRADING OF ENTIRE SITE. ALL TREES SHALL BE REMOVED UNLESS OTHERWISE NOTED IN PLANS OR DIRECTED BY OWNER.
- 2. EXCAVATED MATERIAL THAT IS SUITABLE MAY BE USED FOR FILLS. ALL UNSUITABLE MATERIAL AND ALL SURPLUS EXCAVATED MATERIAL NOT REQUIRED SHALL BE REMOVED FROM THE SITE. THE LOCATION OF DUMP AND LENGTH OF HAUL SHALL BE THE CONTRACTOR'S RESPONSIBILITY.
- 3. PROVIDE AND PLACE ANY ADDITIONAL FILL MATERIAL FROM OFF THE SITE AS MAY BE NECESSARY TO PRODUCE THE GRADES REQUIRED. FILL OBTAINED FROM OFF SITE SHALL BE OF KIND AND QUALITY AS SPECIFIED FOR FILLS HEREIN AND THE SOURCE APPROVED BY THE OWNER. 4. THE CONTRACTOR SHALL ACCEPT THE SITE AS HE FINDS IT AND SHALL REMOVE ALL TRASH,
- A. MAINTAIN CAREFULLY ALL BENCH MARKS, MONUMENTS AND OTHER REFERENCE POINTS; IF DISTURBED OR
- DESTROYED, CONTRACTOR SHALL CONTACT ENGINEER. . REMOVAL OF TREES
- A. THE INTEGRITY OF THE TOPOGRAPHIC FEATURES (INCLUDING TREES) SHALL BE PERSEVERED AS MUCH AS POSSIBLE THE CONTRACTOR SHALL COORDINATE WITH OWNER AND/OR ENGINEER PRIOR TO CLEARING THE SITE FOR CONSTRUCTION.
- B. ALL BRUSH, STUMPS, WOOD AND OTHER REFUSE FROM THE TREES REMOVED SHALL BE HAULED TO DISPOSAL AREAS OFF OF THE SITE. DISPOSAL BY BURNING SHALL NOT BE PERMITTED UNLESS PROPER 7. TRAFFIC AND LANE MARKINGS PERMITS ARE OBTAINED (WHERE APPLICABLE).

RUBBISH AND DEBRIS FROM THE SITE PRIOR TO STARTING EXCAVATION

- . HANDLING OF TOPSOIL A. REMOVE ALL ORGANIC MATERIAL FROM THE AREAS TO BE OCCUPIED BY BUILDINGS, ROADS, WALKS AND PARKING AREAS. PILE AND STORE TOPSOIL AT A LOCATION WHERE IT WILL NOT INTERFERE WITH CONSTRUCTION OPERATIONS. TOPSOIL SHALL BE REASONABLE FREE FROM SUBSOIL, DEBRIS, WEEDS,
- GRASS, STONES, ETC B. AFTER COMPLETION OF SITE GRADING AND SUBSURFACE UTILITY INSTALLATION, TOPSOIL SHALL BE REPLACED IN AREAS DESIGNATED ON THE EROSION CONTROL PLAN FOR SEEDING AND/OR SODDING. ANY REMAINING TOPSOIL SHALL BE USED FOR FINISHED GRADING AROUND STRUCTURES AND LANDSCAPING 8. FIELD QUALITY CONTROL
- 5. DISPOSITION OF UTILITIES
  - A. RULES AND REGULATIONS GOVERNING THE RESPECTIVE UTILITIES SHALL BE OBSERVED IN EXECUTING ALL WORK UNDER THIS SECTION B. IF ACTIVE UTILITIES ARE ENCOUNTERED BUT NOT SHOWN ON THE DRAWINGS, THE ENGINEER SHALL BE
- ADVISED BEFORE WORK IS CONTINUED. INACTIVE AND ABANDONED UTILITIES ENCOUNTERED IN EXCAVATING AND GRADING OPERATIONS SHALL BE REPORTED TO THE ENGINEER. THEY SHALL BE REMOVED, PLUGGED OR CAPPED AS DIRECTED BY THE
- UTILITY COMPANY OR THE ENGINEER. IT SHALL BE THE RESPONSIBILITY OF EACH CONTRACTOR TO VERITY ALL EXISTING UTILITIES AND CONDITIONS PERTAINING TO HIS PHASE OF THE WORK. IT SHALL ALSO BE THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE OWNERS OF THE VARIOUS UTILITIES BEFORE WORK IS STARTED.
- . SITE GRADING GRADES: CONTRACTOR SHALL PERFORM ALL CUTTING, FILLING, COMPACTING OF FILLS AND ROUGH GRADING REQUIRED TO BRING ENTIRE PROJECT AREA TO GRADE AS SHOWN ON THE DRAWINGS. B. ROUGH GRADING: THE TOLERANCE FOR PAVED AREAS SHALL NOT EXCEED 0.10 FEET PLUS OR MINUS ABOVE THE ESTABLISHED SUBGRADE. ALL OTHER AREAS SHALL NOT EXCEED 0.10 FEET PLUS OR MINUS THE ESTABLISHED GRADE. ALL BANKS AND OTHER BREAKS IN GRADE SHALL BE ROUNDED AT THE TOP
- C. COMPACTION REQUIREMENTS: ALL BUILDING PAD AREAS SHALL BE COMPACTED TO STANDARDS SPECIFIED BY LOCAL AND/OR STATE BUILDING CODES.
- COMPACTION REQUIREMENTS OF PAVED AREAS SHALL BE 95% OF MAXIMUM DRY DENSITY. EARTH WORK BALANCE A. THE CONTRACTOR SHALL CONFIRM ALL EARTHWORK QUANTITIES PRIOR TO START OF CONSTRUCTION. IF AN EXCESS OR SHORTAGE OF EARTH IS ENCOUNTERED, THE CONTRACTOR SHALL CONFIRM WITH THE OWNER AND ENGINEER THE REQUIREMENTS FOR STOCKPILING, REMOVAL OR IMPORTING OF EARTH.

MINOR ADJUSTMENTS TO THE GRADES MAY BE REQUIRED TO EARTHWORK BALANCES WHEN MINOR EXCESS MATERIAL OR SHORTAGES ARE ENCOUNTERED. IT IS RECOGNIZED BY THE PARTIES HERETO THAT THE CALCULATIONS OF THE ENGINEER IN ACCORDANCE WITH THE AMERICAN SOCIETY OF CIVIL ENGINEERS STANDARDS FOR SUCH CALCULATIONS. FURTHER. THAT THESE CALCULATIONS ARE SUBJECT TO THE INTERPRETATIONS OF SOIL BORINGS AS THE PHYSICAL LIMITS IN FINISH GRADE AND COMPACTION PERMITTED THE CONTRACTOR, AND THAT ALL OF THESE PARAMETERS MAY CAUSE EITHER AN EXCESS OR SHORTAGE OF ACTUAL EARTHWORK MATERIALS TO COMPLETE THE PROJECT. IF SUCH AN ACTUAL MINOR EXCESS OR SHORTAGE OF ACTUAL EARTHWORK MATERIALS OCCURS, THE CONTRACTOR SHALL CONTACT THE ENGINEER TO DETERMINE IF ADJUSTMENTS CAN BE MADE TO CORRECT THE IMBALANCE OF

- . SCOPE OF WORK
- A. THE WORK REQUIRED UNDER THIS SECTION INCLUDES ALL CONCRETE AND BITUMINOUS PAVING AND RELATED ITEMS NECESSARY TO COMPLETE THE WORK INDICATED ON THE DRAWINGS AND DESCRIBED IN THE SPECIFICATIONS. INCLUDING BUT NOT LIMITED TO ALL STREETS, PARKING AREAS WITHIN THE CONTRACT LIMITS.
- CURBS AND CONCRETE RAMPS
- SIDEWALKS AND CONCRETE SLABS. 4. IN THE CASE OF ANY CONFLICTS WITH THESE SPECIFICATIONS AND LOCAL, STATE, FEDERAL SPECIFICATIONS THE MORE STRINGENT SHALL APPLY. B. IN THE CASE OF ANY CONFLICTS WITH THESE SPECIFICATIONS AND LOCAL, STATE, FEDERAL
- SPECIFICATIONS THE MORE STRINGENT SHALL APPLY. . PAVEMENT CONSTRUCTION A. ALL STREET CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS AND
- CONFORM TO THE MINIMUM STANDARDS OF THE JOHNSON COUNTY PLANNING AND HIGHWAY DEPARTMENTS, AND IF THERE ARE AREAS UNDEFINED USE THE MOST CURRENT I.N.D.O.T. STANDARD SPECIFICATION B. FLEXIBLE PAVEMENT MATERIALS
  - A. GENERAL: USE LOCALLY AVAILABLE MATERIALS AND GRADATIONS WHICH EXHIBIT A SATISFACTORY RECORD OF PREVIOUS INSTALLATIONS.
  - B. COMPACTED AGGREGATE BASE: SOUND. ANGULAR CRUSHED LIMESTONE. CRUSHED OR UNCRUSHED GRAVEL, OR CRUSHED OR PROCESSED AIR-COOLED BLAST FURNACE SLAG. COURSE AGGREGATE SHALL BE CLASS A, TYPE "O" AND CONFORM TO THE MOST CURRENT I.N.D.O.T. STANDARD SPECIFICATION.
  - C. BASE COURT AGGREGATE: SOUND, ANGULAR CRUSHED STONE, CRUSHED OR UNCRUSHED GRAVEL, OR CRUSHED SLAG, SAND, STONE, OR SLAG SCREENINGS. COARSE AGGREGATES SHALL BE CLASS A OR B AND CONFORM TO I.N.D.O.T. STANDARDS SPECIFICATIONS SECTION 903.
  - D. COARSE AGGREGATE FOR SURFACE AND BINDER MIXTURES: CRUSHED STONE, CRUSHED GRAVEL, CRUSHED SLAB, AND SHARP EDGED NATURAL SAND. SURFACE COARSE AGGREGATES SHALL BE CLASS A AND CONFORM TO I.N.D.O.T. STANDARD SPECIFICATIONS SECTION 903.
- 3. ASPHALT—AGGREGATE MIXTURE
  - ALL BITUMINOUS MIXTURES ARE TO CONFORM TO CURRENT I.N.D.O.T. SPECIFICATIONS
  - SURFACE COURSE: HMA SURFACE 9.5mm B. BINDER COURSE: HMA INTERMEDIATE 19.0mm
  - BASE COURSE: TYPE: HMA BASE 25.0mm \*\*PROVIDED A JOB MIX FORMULA FOR EACH TYPE OF ASPHALT PRIOR TO THE BEGINNING OF THE CONSTRUCTION PROJECT.
- L. SURFACE PREPARATION A. REMOVE LOOSE MATERIAL FROM COMPACTED SUBBASE SURFACE IMMEDIATELY BEFORE APPLYING PRIME
  - I) PROOF ROLL SUBGRADE SURFACE WITH LOADED TRI-AXLE TRUCK (48 HOUR NOTICE IS REQUIRED TO BE GIVEN TO THE JOHNSON COUNTY HIGHWAY DEPT.) TO CHECK FOR UNSTABLE AREAS AND AREAS REQUIRING ADDITIONAL COMPACTION.
  - II) NOTIFY CONTRACTOR OF UNSATISFACTORY CONDITIONS. DO NOT BEGIN PAVING WORK UNTIL DEFICIENT SUBBASE AREAS HAVE BEEN CORRECTED AND ARE READY TO RECEIVE PAVING. AGGREGATE BASE: AFTER PLACEMENT, PROOF ROLL COMPACTED AGGREGATE BASE SURFACE TO CHECK
  - FOR UNSTABLE AREAS AND AREAS REQUIRING ADDITIONAL COMPACTION. NOTIFY CONTRACTOR OF UNSATISFACTORY CONDITIONS. DO NOT BEGIN PAVING WORK UNTIL DEFICIENT AGGREGATE BASE AREAS HAVE BEEN CORRECTED AND ARE READY TO RECEIVE PAVING.
- II) REMOVE LOOSE MATERIAL FROM COMPACTED AGGREGATE BASE SURFACE IMMEDIATELY BEFORE APPLYING PRIME COAT. 5. PLACING THE MIX A. GENERAL: PLACE BITUMINOUS AGGREGATE MIXTURE ON PREPARED SURFACE, SPREAD AND STRIKE-OFF.
- SPREAD MIXTURE AT MINIMUM TEMPERATURE OF 225 DEGREES F.(107 DEGREES C). PLACE INACCESSIBLE AND SMALL AREAS BY HAND. PLACE EACH COURSE TO REQUIRED GRADE, CROSS-SECTION, AND COMPACTED THICKNESS
- B. BASE COURSE, COMPACTED AGGREGATE: SPREAD AND COMPACT IN TWO LIFTS AS FOLLOWS: I) FIRST LIFT: NO. 5'S SHALL BE A MINIMUM OF 4" OR ½ THE TOTAL DEPTH OF AGGREGATE. EXTEND THE FIRS LIFT 4" OR A DISTANCE EQUAL TO THE DEPTH OF THE LIFT BEYOND THE SECOND LIFT.
- II) SECOND LIFT: SIZE NO. 53 PRIME COAT: SUBBASE SURFACE SHALL BE PRIMED IN ACCORDANCE WITH THE APPLICABLE
- REQUIREMENTS OF THE MOST CURRENT I.N.D.O.T. STANDARD SPECIFICATION. HOT ASPHALT CONCRETE BINDER COURSE: SPREAD AND ROLL TO MINIMUM FINISH DEPTHS INDICATED ON
- E. TACK COAT: BINDER COURSE SHALL BE TACKED PRIOR TO THE INSTALLATION OF THE SURFACE COURSE IN ACCORDANCE WITH THE APPLICABLE REQUIREMENTS OF THE MOST CURRENT I.N.D.O.T. STANDARD

#### F. SURFACE COURSE: SPREAD AND ROLL TO MINIMUM FINISH DEPTH INDICATED ON DETAILS. FINISH STORM SEWER SYSTEMS ELEVATION SHALL BE TRUE TO LINE AND GRADE WITHIN 1/2" OF TRUE ELEVATIONS.

- G. PAVER PLACING: PLACE IN STRIPS NOT LESS THAN 10' WIDE, UNLESS OTHERWISE ACCEPTABLE TO 1. SCOPE OF WORK ARCHITECT/ENGINEER. AFTER FIRST STRIP HAS BEEN PLACED AND ROLLED, PLACE SUCCEEDING STRIPS

  A. THE WORK UNDER THIS SECTION INCLUDES ALL STORM SEWERS, STORM WATER INLETS, AND RELATED ITEMS, AND EXTEND ROLLING TO OVERLAP PREVIOUS STRIPS. COMPLETE BINDER COURSE FOR A SECTION BEFORE PLACING SURFACE COURSE.
- H. JOINTS: MAKE JOINTS BETWEEN OLD AND NEW PAVEMENTS, OR BETWEEN PAVER PASSES. OR BETWEEN SUCCESSIVE DAYS WORK, TO ENSURE CONTINUOUS BOND BETWEEN ADJOINING WORK. CONSTRUCT JOINTS 2. STORM SEWER CONSTRUCTION TO HAVE SAME TEXTURE, DENSITY AND SMOOTHNESS AS OTHER SECTIONS. CLEAN CONTACT SURFACES AND APPLY TACT COAT.
- GENERAL: BEGIN ROLLING WHEN MIXTURE WILL BEAR ROLLER WEIGHT WITHOUT EXCESSIVE DISPLACEMENT. I) COMPACT MIXTURE WITH HOT HAND TAMPERS OR VIBRATING PLATE COMPACTORS IN AREAS
- INACCESSIBLE TO ROLLERS B. BREAKDOWN ROLLING: ACCOMPLISH BREAKDOWN OR INITIAL ROLLING IMMEDIATELY FOLLOWING ROLLING OF JOINTS AND OUTSIDE EDGE. CHECK SURFACE AFTER BREAKDOWN ROLLING, AND REPAIR DISPLACED

AREAS BY LOOSENING AND FILLING. IF REQUIRED. WITH HOT MATERIAL

- C. SECOND ROLLING: FOLLOW BREAKDOWN ROLLING AS SOON AS POSSIBLE. WHICH MIXTURE IS HOT. CONTINUE SECOND ROLLING UNTIL MIXTURE HAS BEEN THOROUGHLY COMPACTED. D. FINISH ROLLING: PERFORM FINISH ROLLING WHILE MIXTURE IS STILL WARM ENOUGH FOR REMOVAL OF ROLLER MARKS. CONTINUE ROLLING UNTIL ROLLER MARKS ARE ELIMINATED AND COURSE HAS ATTAINED MAXIMUM DENSITY.
- E. PATCHING: REMOVE AND REPLACE PAVING AREAS MIXED WITH FOREIGN MATERIALS AND DEFECTIVE AREAS. CUT OUT SUCH AREAS AND FILL WITH FRESH, HOT BITUMINOUS AGGREGATE MIX. COMPACT BY ROLLING TO MAXIMUM SURFACE DENSITY AND SMOOTHNESS. F. PROTECTION: AFTER FINAL ROLLING, DO NOT PERMIT VEHICULAR TRAFFIC ON PAVEMENT UNTIL IT HAS COOLED AND HARDENED.
- ERECT BARRICADES TO PROTECT PAVING FROM TRAFFIC UNTIL MIXTURE HAS COOLED ENOUGH NOT TO BECOME MARKED.
- A. CLEANING: SWEEP AND CLEAN SURFACE TO FLIMINATE LOOSE MATERIAL AND DUST. B. STRIPPING: USE CHLORINATED RUBBER BASE TRAFFIC LANE-MARKING PAINT, FACTORY MIXED, QUICK-DRYING, AND NON-BLEEDING.
- COLOR: YELLOW I) DO NOT APPLY TRAFFIC AND LANE MARKING PAINT UNTIL LAYOUT AND PLACEMENT HAS BEEN
- VERIFIED WITH ARCHITECT/ENGINEER. II) APPLY PAINT WITH MECHANICAL EQUIPMENT TO PRODUCE UNIFORM STRAIGHT EDGES. APPLY IN TWO COATS AT MANUFACTURER'S RECOMMENDED RATES.
- A. TESTING AND INSPECTION SERVICE:
- I) OWNER SHALL EMPLOY A TESTING LABORATORY TO PERFORM PAVEMENT TESTING AND INSPECTION SERVICE FOR QUALITY CONTROL DURING PAVING OPERATIONS. II) TESTING SERVICE SHALL HAVE REPRESENTATIVE PRESENT TO OBSERVE AND PERFORM TESTS AT ALL TIMES PAVING WORK IS IN PROGRESS
- B. GENERAL: TESTING SERVICE REPRESENTATIVE SHALL TAKE A MINIMUM OF TWO SAMPLES PER LIFT OF BITUMINOUS AGGREGATE MIX EACH DAY BEFORE PAVING OPERATION. LABORATORY TEST SHALL BE PERFORMED ON THESE SAMPLES TO DETERMINE AGGREGATE GRADATION AND ASPHALT CONTENT. I) TEST IN-PLACE COMPACTED BITUMINOUS AGGREGATE MIX COURSES FOR COMPLIANCE WITH REQUIREMENTS FOR THICKNESS, DENSITY AND AIR VOIDS AND SURFACE SMOOTHNESS. REPAIR OR
- REMOVE AND REPLACE UNACCEPTABLE PAVING AS DIRECTED BY ENGINEER II) A TEST SECTION AT A MINIMUM SIZE OF 100'X12' SHALL BE PLACED AT A LOCATION AS DIRECTED BY THE COUNTY PRIOR TO FULL PRODUCTION FOR EACH TYPE OF MIX. THE TEST SECTION SHALL
- BE COMPACTED TO DETERMINE A TARGET DENSITY FOR THE REMAINDER OF THE PAVEMENT. C. THICKNESS: IN-PLACE COMPACTED THICKNESS WILL NOT BE ACCEPTABLE IF EXCEEDING FOLLOWING ALLOWABLE VARIATION FROM REQUIRED THICKNESS: AGGREGATE BASE COURSE: 1/2", PLUS OR MINUS
- BASE COURSE: 1/2", PLUS OR MINUS BINDER COURSE: 1/4", PLUS OR MINUS
- SURFACE COURSE: 1/4", PLUS OR MINUS D. PAVEMENT THICKNESS
- DENSITY
- I) TESTING SERVICE SHALL SUBMIT CERTIFIED RESULTS TO THE OWNER AND ARCHITECT/ENGINEER WITHIN 72 HOURS AFTER TESTS ARE MADE, WITH THEIR COMMENTS AND RECOMMENDATIONS FOR
- II) PAVEMENT WHICH FAILS TO COMPLY WITH APPROVED JOB MIX FORMULA SHALL BE REPLACED AS DIRECTED BY THE ARCHITECT/ENGINEER.
- E. SURFACE SMOOTHNESS: TEST FINISHED SURFACE FOR SMOOTHNESS, USING 10' STRAIGHTEDGE APPLIED PARALLEL WITH, AND AT RIGHT ANGLES TO CENTERLINE OF PAVED AREA. SURFACE WILL NOT BE ACCEPTABLE IF EXCEEDING THE FOLLOWING TOLERANCES FOR SMOOTHNESS. AGGREGATE BASE COURSE SURFACE: 1/4"
  - BASE COURSE SURFACE: 1/4" BINDER COURSE SURFACE: 1/8"
- WEARING COURSE SURFACE: 1/8"
- I) CHECK SURFACED AREAS AT INTERVALS AS DIRECTED BY TESTING SERVICE. F. DENSITY TESTS: DENSITY TESTS SHALL BE MADE AT EACH LIFT. TEST SHALL BE AS FOLLOWS: I) TESTS WILL BE REQUIRED AT VARIOUS TIMES AND LOCATIONS FOR SUBGRADE AND BASE COURSES 2. MATERIALS FOR ASPHALT PAVING AREAS.
- G. TESTING SERVICE SHALL SUBMIT CERTIFIED RESULTS TO THE OWNER AND ENGINEER WITHIN 72 HOURS AFTER TESTS ARE MADE WITH THEIR COMMENTS AND RECOMMENDATIONS FOR ACTION. I) SUBGRADE SHALL BE PREPARED IN ACCORDANCE WITH THE MOST CURRENT I.N.D.O.T. STANDARD
- SPECIFICATION. NO TRAFFIC SHALL BE PERMITTED ON THE PREPARED SUBGRADE PRIOR TO PAVING. II) SEE SITE GRADING, UNDER THE 'EARTHWORK' SECTION FOR ADDITIONAL COMPACTION REQUIREMENTS.
- A. GRADING: DO ANY NECESSARY GRADING IN ADDITION TO THAT PERFORMED IN ACCORDANCE WITH EARTHWORK SECTION TO BRING SUBGRADES, AFTER FINAL COMPACTION, TO THE REQUIRED GRADES AND
- SECTIONS FOR SITE IMPROVEMENTS B. PREPARATION OF SUBGRADE: REMOVE SPONGY AND OTHERWISE UNSUITABLE MATERIAL AND REPLACE WITH STABLE MATERIAL. NO TRAFFIC WILL BE ALLOWED ON PREPARED SUBGRADE PRIOR TO PAVING. C. COMPACTION OF SUBGRADE: THE FIRST 6 INCHES BELOW THE SUBGRADE SHALL BE COMPACTED TO AT

LEAST 100% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY THE PROVISIONS OF AASHO T-99.

- WATER SHALL BE PREVENTED FROM STANDING ON THE COMPACTED SUBGRADE. D. UTILITY STRUCTURES: CHECK FOR CORRECT ELEVATION OF ALL MANHOLE COVERS, VALVE BOXES AND SIMILAR STRUCTURES LOCATED WITHIN AREAS TO BE PAVED, AND MAKE, OR HAVE MADE, ANY NECESSARY ADJUSTMENTS IN SUCH STRUCTURES.
- E. PLACING CONCRETE 1. SUBGRADE: PLACE CONCRETE ONLY ON A MOIST, COMPACTED SUBGRADE OR BASE FREE FROM LOOSE MATERIAL. PLACE NO CONCRETE ON A MUDDY OR FROZEN SUBGRADE. 2. FORMS: ALL FORMS SHALL BE FREE FROM WARP, TIGHT ENOUGH TO PREVENT LEAKAGE AND SUBSTANTIAL ENOUGH TO MAINTAIN THEIR SHAPE AND POSITION WITHOUT SPRINGING OR SETTLING,
- CONCRETING. 3. PLACING CONCRETE: CONCRETE SHALL BE DEPOSITED SO AS TO REQUIRE AS LITTLE REHANDLING AS PRACTICABLE. WHEN CONCRETE IS TO BE PLACED AT AN ATMOSPHERIC TEMPERATURE OF 35 DEGREES F. OR LESS, THE MOST CURRENT I.N.D.O.T. STANDARD SPECIFICATIONS SHALL BE FOLLOWED.

WHEN CONCRETE IS PLACED. FORMS SHALL BE CLEAN AND SMOOTH IMMEDIATELY BEFORE

- F. CONCRETE CURB 1. EXPANSION JOINTS: SHALL BE 1/2 INCH THICK PREMOULDED AT ENDS OF ALL RETURNS AND AT A MAXIMUM SPACING OF 100 FEET. 2. CONTRACTION JOINTS UNLESS OTHERWISE PROVIDED, CONTRACTION JOINTS SHALL BE SAWED JOINTS
- SPACED 10 FEET ON CENTER. 3. FINISH: TAMP AND SCREED CONCRETE AS SOON AS PLACED, AND FILL ANY HONEY COMBED PLACES. FINISH SQUARE CORNERSTONE 1/4 INCH RADIUS AND OTHER CORNERS TO RADII SHOWN.
- G. CONCRETE WALKS AND EXTERIOR STEPS 1. SLOPES: PROVIDE 1/4 INCH PER FOOT CROSS SLOPE. MAKE ADJUSTMENTS ON SLOPES AT WALK INTERSECTIONS AS NECESSARY TO PROVIDE PROPER DRAINAGE. 2. DIMENSIONS: WALKS AND STEPS SHALL BE ONE COURSE CONSTRUCTION AND OF WIDTHS AND DETAILS
- SHOWN ON THE DRAWINGS. 3. FINISH: SCREED CONCRETE AND TROWEL WITH A STEEL TROWEL TO A HARD DENSE SURFACE AFTER
- SURFACE WATER HAS DISAPPEARED. APPLY MEDIUM BROOM FINISH AND SCRIBE TRANSVERSE JOINTS AT 6 FOOT SPACING. PROVIDE 1/2 INCH EXPANSION JOINTS WHERE SIDEWALKS INTERSECT, AND AT A MAXIMUM SPACING OF 48 FEET BETWEEN EXPANSION JOINTS. H. CURING CONCRETE FOR WALKS AND CURBS: EXCEPT AS OTHERWISE SPECIFIED, CURE ALL CONCRETE BY ONE OF THE METHODS DESCRIBED IN THE MOST CURRENT I.N.D.O.T. STANDARD SPECIFICATION.

I. BITUMINOUS PAVEMENT: HOT MIX ASPHALT PAVEMENT SHALL BE AS SPECIFIED IN THE MOST CURRENT

- I.N.D.O.T. STANDARD SPECIFICATION. PAVING WILL NOT BE PERMITTED DURING UNFAVORABLE WEATHER OR THEN THE TEMPERATURE IS 40 DEGREES F. AND FALLING J. COMPACTED AGGREGATE SUBBASE: THE THICKNESS SHOWN ON THE DRAWINGS IS THE MINIMUM THICKNESS OF THE FULL COMPACTED SUBBASE. COMPACTION SHALL BE ACCOMPLISHED BY ROLLING WITH A SMOOTH WHEELED ROLLER WEIGHING 8 TO 10 TONS. COMPACT TO 95% COMPACTION USING STANDARD TESTING PROCEDURES. ALONG CURBS. HEADERS AND WALLS AND AT ALL PLACES NOT ACCESSIBLE TO THE ROLLER, THE AGGREGATE MATERIAL SHALL BE TAMPED WITH MECHANICAL TAMPERS OR WITH APPROVED
- 1. CONCRETE RAMPS FOR THE DISABLED SHALL BE REQUIRED AS SPECIFIED IN THE PLANS AND SHALL CONFORM WITH CURRENT SPECIFICATIONS ESTABLISHED BY THE AMERICAN DISABILITIES ACT (ADA),
- SECTION 4.7, "CURB RAMPS." 2. THE CONCRETE RAMP SHALL BE FLUSH AND FREE OF ABRUPT CHANGES WITH SIDEWALKS, GUTTERS OR STREETS, AND PROVIDE A MAXIMUM SLOPE OF 1:12. 3. THE MINIMUM WIDTH OF A CONCRETE RAMP SHALL BE (48) INCHES EXCLUSIVE OF FLARED SIDES.

4. SIDES OF CONCRETE RAMPS SHALL HAVE FLARED SIDES AS SHOWN IN THE PLANS.

- INCLUDING EXCAVATING AND BACKFILLING NECESSARY TO COMPLETE THE WORK SHOWN ON THE DRAWINGS. B. IN THE CASE OF ANY CONFLICTS WITH THESE SPECIFICATIONS AND LOCAL, STATE, FEDERAL SPECIFICATIONS
- THE MORE STRINGENT SHALL APPLY.
- A. STORM SEWERS 1. STORM SEWER STRUCTURES SHALL COMPLY WITH CURRENT SPECIFICATIONS OF THE JOHNSON COUNTY
- ENGINEERING DEPARTMENT AND ALL OTHER RESPONSIBLE AGENCIES IN RESPECT TO DESIGN AND QUALITY OF CONSTRUCTION.
- 2. ALL STORM SEWER CONSTRUCTION INSIDE PUBLIC RIGHT-OF-WAY, EITHER EXISTING OR TO BE DEDICATED, SHALL BE IN ACCORDANCE WITH THE MOST CURRENT I.N.D.O.T. STANDARD SPECIFICATION. 3. WHERE REINFORCED CONCRETE PIPE IS SHOWN ON THE CONSTRUCTION PLANS, IT SHALL BE IN ACCORDANCE WITH A.S.T.M. C-76 CLASS III WALL "C" UNLESS OTHERWISE SPECIFIED ON THE PLANS
- 4. WHERE CORRUGATED METAL PIPE IS SHOWN ON THE CONSTRUCTION PLANS. IT SHALL BE 14 GAUGE ALUMINIZED UNLESS OTHERWISE SPECIFIED AND SHALL HAVE THE CONNECTING BANDS AND SEALS AS SPECIFIED BY THE MANUFACTURER. C.M.P. SHALL BE ALUMINIZED PIPE IN ACCORDANCE WITH A.S.T.M.
- 5. MANHOLES, CATCH BASINS AND INLETS SHALL BE PRECAST CONCRETE.
- A. IF THE CONTRACTOR ELECTS TO USE ALTERNATE PRECAST STRUCTURES, HE SHALL SUBMIT SHOP

  3. APPLICATION

  DRAWNOS TO THE ENGINEER PRIOR TO ANY CONTRACTOR. DRAWINGS TO THE ENGINEER PRIOR TO ANY CONSTRUCTION. 6. PRECAST CONCRETE AND STEEL FOR MANHOLES AND INLETS SHALL BE IN ACCORDANCE WITH A.S.T.M.
- 7. CASTINGS SHALL BE AS SHOWN ON THE DETAIL SHEET(S) FOR MANUFACTURER, TYPE AND MODEL NUMBER. 8. GRANULAR BACKFILL SHALL BE REQUIRED UNDER ALL PAVEMENT AREAS AND TRENCHES WITHIN FIVE(5) FEET OF THE EDGE OF PAVEMENT.
- 9. ALL TRENCHES UNDER PAVEMENT SHALL BE COMPACTED TO 95 PERCENT MODIFIED PROCTOR. 3. APPLICATION A. PERMITS AND CODES: THE INTENT OF THIS SECTION OF THE SPECIFICATIONS IS THAT THE CONTRACTOR'S BID
- ON THE WORK COVERED HEREIN SHALL BE BASED UPON THE DRAWINGS AND SPECIFICATIONS BUT THAT THE WORK SHALL COMPLY WITH ALL APPLICABLE CODES AND REGULATIONS AS AMENDED BY ANY WAIVERS. THE CONTRACTOR SHALL FURNISH ALL BONDS NECESSARY TO GET PERMITS FOR CUTS AND CONNECTIONS TO EXISTING SEWERS
- B. LOCAL STANDARDS: THE TERM "LOCAL STANDARDS" AS USED HEREIN MEANS THE STANDARDS OF DESIGN AND CONSTRUCTION OF THE RESPECTIVE MUNICIPAL DEPARTMENT OR UTILITY COMPANY. C. EXISTING IMPROVEMENTS: THE CONTRACTOR SHALL MAINTAIN IN OPERATING CONDITION ALL ACTIVE UTILITIES, SEWERS AND OTHER DRAINS ENCOUNTERED IN THE SEWER INSTALLATION. THE CONTRACTOR SHALL REPAIR TO THE SATISFACTION OF THE OWNER ANY DAMAGE TO EXISTING ACTIVE IMPROVEMENTS.
- APPROVED BY ALL LOCAL AND STATE AGENCIES HAVING JURISDICTION. TRENCHING: LAY ALL PIPE IN OPEN TRENCHES. EXCEPT WHEN THE LOCAL AUTHORITY GIVES WRITTEN PERMISSION FOR TUNNELING. OPEN THE TRENCH SUFFICIENTLY AHEAD OF PIPE-LAYING TO REVEAL ANY OBSTRUCTIONS. THE MIN. WIDTH OF TRENCH SHALL BE 1.25 TIMES THE OUTSIDE DIA. OF PIPE. SHEET AND BRACE TRENCH AS NECESSARY TO PROTECT WORKMEN AND ADJACENT STRUCTURES. ALL TRENCHING TO COMPLY WITH OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION STANDARDS. KEEP TRENCHES FREE FROM WATER WHILE CONSTRUCTION IS IN PROGRESS. UNDER NO CIRCUMSTANCES SHALL PIPE OR APPURTENANCES BE LAID IN STANDING WATER. CONDUCT THE DISCHARGE FROM TRENCH DE-WATERING TO DRAINS OR

D. WORKMANSHIP: THIS WORK SHALL CONFORM TO ALL LOCAL, STATE AND NATIONAL CODES AND TO BE

- F. SPECIAL SUPPORTS: WHENEVER, IN THE OPINION OF THE ENGINEER, THE SOIL AT OR BELOW THE PIPE GRADE IS UNSUITABLE FOR SUPPORTING SEWERS AND APPURTENANCES SPECIFIED IN THIS SECTION, SUCH SPECIAL SUPPORT, IN ADDITION TO THOSE SHOWN OR SPECIFIED, SHALL BE PROVIDED AS THE ENGINEER MAY DIRECT, AND THE CONTRACT WILL BE ADJUSTED.
- G. BACKFILLING: BACKFILL SHALL BE PLACED AS SHOWN IN THE PLANS. NOTE THAT PVC & HDPE PIPE SHALL BE COVERED WITH 12" MINIMUM OF #8 STONE. COMPACT THIS BACKFILL THOROUGHLY, TAKING CARE NOT TO DISTURB THE PIPE. BACKFILL UNDER AND WITHIN 5 FEET OF WALKS, PARKING AREAS, DRIVEWAYS AND STREETS SHALL BE "B" BORROW OR EQUIVALENT GRANULAR MATERIAL ONLY AND THOROUGHLY COMPACTED BY APPROVED METHODS
- H. MANHOLE INVERTS: CONSTRUCT MANHOLE FLOW CHANNELS OF CONCRETE SEWER PIPE OR BRICK, SMOOTHLY FINISHED AND OF SEMICIRCULAR SECTION CONFORMING TO THE INSIDE DIAMETER OF THE CONNECTING SEWERS. MAKE CHANGES IN SIZE OR GRADE GRADUALLY AND CHANGES INDIRECTION BY TRUE CURVES.
- PROVIDE SUCH CHANNELS FOR ALL CONNECTING SEWERS AT EACH MANHOLE. SUBDRAINS: ALL SUBDRAINS SHALL BE OF THE SIZE SHOWN ON THE PLANS AND SHALL BE CONSTRUCTED TO THE GRADES SHOWN. ALL DRAINS CONSTRUCTED OFF-SITE AS PART OF THE OUTLET DRAIN WILL BE LOCATED
- J. UTILITIES: IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERITY ALL EXISTING UTILITIES AND CONDITIONS PERTAINING TO HIS WORK. IT SHALL ALSO BE THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE OWNERS OF THE VARIOUS UTILITIES BEFORE WORK IS STARTED. THE CONTRACTOR SHALL NOTIFY IN WRITING THE OWNER AND THE ENGINEER OF ANY CHANGES, ERRORS OR OMISSIONS FOUND ON THESE PLANS OR IN THE FIELD BEFORE WORK IS STARTED OR RESUMED.

#### WATER LINE SYSTEM

NATURAL DRAINAGE CHANNELS.

- A. THE WORK UNDER THIS SECTION INCLUDES ALL WATER MAIN, FIRE HYDRANTS, SERVICES AND RELATED ITEMS. INCLUDING EXCAVATING AND BACKFILLING NECESSARY TO COMPLETE THE WORK SHOWN ON THE DRAWINGS.
- A. ALL MATERIALS SHALL CONFORM TO ALL LOCAL, STATE, AND NATIONAL CODES AND SHALL BE APPROVED BY
- ALL LOCAL AND STATE AGENCIES HAVING JURISDICTION. A. PERMITS AND CODES: THE INTENT OF THIS SECTION OF THE SPECIFICATIONS IS THAT THE CONTRACTOR'S BID ON THE WORK COVERED HEREIN SHALL BE BASED UPON THE DRAWINGS AND SPECIFICATIONS BUT THAT THE WORK SHALL COMPLY WITH ALL APPLICABLE CODES AND REGULATIONS AS AMENDED BY ANY WAIVERS. TH
- CONTRACTOR SHALL FURNISH ALL BONDS NECESSARY TO GET PERMITS FOR CUTS AND CONNECTIONS TO EXISTING WATER MAINS. B. LOCAL STANDARDS: THE TERM "LOCAL STANDARDS" AS USED HEREIN MEANS THE STANDARDS OF DESIGN AND CONSTRUCTION OF THE RESPECTIVE MUNICIPAL DEPARTMENT OR UTILITY COMPANY.
- EXISTING IMPROVEMENTS: THE CONTRACTOR SHALL MAINTAIN IN OPERATING CONDITION ALL ACTIVE UTILITIES, SEWERS AND OTHER DRAINS ENCOUNTERED IN THE WATER LINE INSTALLATION. THE CONTRACTOR SHALL REPAIR TO THE SATISFACTION OF THE OWNER ANY DAMAGE TO EXISTING ACTIVE IMPROVEMENTS. D. WORKMANSHIP: THIS WORK SHALL CONFORM TO ALL LOCAL. STATE AND NATIONAL CODES AND TO BE
- APPROVED BY ALL LOCAL AND STATE AGENCIES HAVING JURISDICTION. THIS INCLUDES ALL REQUIRED CLEANING AND TESTING PROCEDURES REQUIRED BY THE STATE AND LOCAL AGENCIES. TRENCHING: LAY ALL PIPE IN OPEN TRENCHES, EXCEPT WHEN THE LOCAL AUTHORITY GIVES WRITTEN PERMISSION FOR TUNNELING, OPEN THE TRENCH SUFFICIENTLY AHEAD OF PIPE-LAYING TO REVEAL ANY OBSTRUCTIONS. THE MIN. WIDTH OF TRENCH SHALL BE 1.25 TIMES THE OUTSIDE DIA. OF PIPE. SHEET AND BRACE TRENCH AS NECESSARY TO PROTECT WORKMEN AND ADJACENT STRUCTURES. ALL TRENCHING TO COMPLY WITH OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION STANDARDS. KEEP TRENCHES FREE FROM WATER WHILE CONSTRUCTION IS IN PROGRESS. UNDER NO CIRCUMSTANCES SHALL PIPE OR APPURTENANCES BE LAID IN STANDING WATER. CONDUCT THE DISCHARGE FROM TRENCH DE-WATERING TO DRAINS OR
- NATURAL DRAINAGE CHANNELS F. SPECIAL SUPPORTS: WHENEVER, IN THE OPINION OF THE ENGINEER, THE SOIL AT OR BELOW THE PIPE GRADE IS UNSUITABLE FOR SUPPORTING PIPE AND APPURTENANCES SPECIFIED IN THIS SECTION, SUCH SPECIAL
- SUPPORT, IN ADDITION TO THOSE SHOWN OR SPECIFIED, SHALL BE PROVIDED AS THE ENGINEER MAY DIRECT, AND THE CONTRACT WILL BE ADJUSTED. G. BACKFILLING: BACKFILL SHALL BE PLACED AS SHOWN IN THE PLANS. NOTE THAT PVC & HDPE PIPE SHALL BE COVERED WITH 12" MINIMUM OF #8 STONE. COMPACT THIS BACKFILL THOROUGHLY, TAKING CARE NOT TO DISTURB THE PIPE, BACKFILL UNDER AND WITHIN 5 FEET OF WALKS, PARKING AREAS, DRIVEWAYS AND STREETS SHALL BE "B" BORROW OR EQUIVALENT GRANULAR MATERIAL ONLY AND THOROUGHLY COMPACTED
- H. UTILITIES: IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY ALL EXISTING UTILITIES AND CONDITIONS PERTAINING TO HIS WORK. IT SHALL ALSO BE THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE OWNERS OF THE VARIOUS UTILITIES BEFORE WORK IS STARTED. THE CONTRACTOR SHALL NOTIFY IN WRITING THE OWNER AND THE ENGINEER OF ANY CHANGES, ERRORS OR OMISSIONS FOUND ON THESE PLANS OR IN THE FIELD BEFORE WORK IS STARTED OR RESUMED.

#### SANITARY SEWER SYSTEMS

- A. THE WORK UNDER THIS SECTION INCLUDES ALL SANITARY SEWERS, MANHOLES, CLEANOUTS AND RELATED ITEMS INCLUDING EXCAVATING AND BACKFILLING, NECESSARY TO COMPLETE THE WORK SHOWN IN THE DRAWINGS, STARTING OUTSIDE THE BUILDING WALLS. THE END OF SEWERS SHALL BE TIGHTLY PLUGGED OF
  - CAPPED AT THE TERMINAL POINTS, ADJACENT TO THE BUILDING DRAIN AS SPECIFIED IN THE PLUMBING SPECIFICATIONS AND/OR ARCHITECTURAL DRAWINGS.
- A. SANITARY SEWERS 1. ALL GRAVITY PLASTIC SEWER PIPE FITTINGS SHALL CONFORM TO ASTM D3034 WITH A CELL CLASSIFICATION OF 12454-B OR 12454-C. FLEXIBLE GASKETED COMPRESSION JOINTS SHALL BE USED FOR PVC & PVC
- TRUSS PIPE, NO SOLVENT CEMENT JOINTS SHALL BE ALLOWED 2. ABS SEWER PIPE AND FITTINGS SHALL CONFORM TO ASTM D2680 LATEST REVISION. 3. TRACER WIRE SHALL BE INSTALLED WITH ALL NEW SANITARY PIPE.
- 1. ALL SANITARY FORCE MAIN PIPE AND FITTINGS SHALL CONFORM TO ASTM D2241, STANDARD SPECIFICATION FOR POLY VINYL CHLORIDE (PVC) PRESSURE-RATED PIPE, (SDR 21, GREATER THAN 4 INCH
- 2. TRACER WIRE SHALL BE INSTALLED WITH ALL SANITARY FORCE MAIN PIPE.
- A PERMITS AND CODES

TRENCHING:

SERVICE LATERALS:

THESE PLANS.


- THE INTENT OF THIS SECTION OF THE SPECIFICATIONS IS THAT THE CONTRACTOR'S BID ON THE WORK COVERED HEREIN SHALL BE BASED LIPON THE DRAWINGS AND SPECIFICATIONS BUT THAT THE WORK SHALL COMPLY WITH ALL APPLICABLE CODES AND REGULATIONS AS AMENDED BY ANY WAIVERS. CONTRACTOR SHALL
- FURNISH ALL BONDS NECESSARY TO GET PERMITS FOR CUTS AND CONNECTIONS TO EXISTING SEWERS. B. LOCAL STANDARDS: THE TERM "LOCAL STANDARDS" AS USED HEREIN MEANS THE STANDARDS OF DESIGN AND CONSTRUCTION OF THE RESPECTIVE MUNICIPAL DEPARTMENT OR UTILITY COMPANY.
- EXISTING IMPROVEMENTS: THE CONTRACTOR SHALL MAINTAIN IN OPERATING CONDITION ALL ACTIVE UTILITIES, SEWERS AND OTHER DRAINS ENCOUNTERED IN THE SEWER INSTALLATION. THE CONTRACTOR SHALL REPAIR TO THE SATISFACTION OF THE OWNER ANY DAMAGE TO EXISTING ACTIVE IMPROVEMENTS.
- WORKMANSHIP. THIS WORK SHALL CONFORM TO ALL LOCAL, STATE AND NATIONAL CODES AND TO BE APPROVED BY ALL LOCAL AND STATE AGENCIES HAVING JURISDICTION.
- LAY ALL PIPE IN OPEN TRENCHES, EXCEPT WHEN THE LOCAL AUTHORITY GIVES WRITTEN PERMISSION FOR TUNNELING. OPEN THE TRENCH SUFFICIENTLY AHEAD OF PIPE-LAYING TO REVEAL ANY OBSTRUCTIONS. THE MIN. WIDTH OF TRENCH SHALL BE 1.25 TIMES THE OUTSIDE DIA. PLUS 12 INCHES. SHEET AND BRACE TRENCH AS NECESSARY TO PROTECT WORKMEN AND ADJACENT STRUCTURES. ALL TRENCHING TO COMPLY WITH OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION STANDARDS. KEEP TRENCHES FREE FROM WATER WHILE CONSTRUCTION IS IN PROGRESS. UNDER NO CIRCUMSTANCES SHALL PIPE OR APPURTENANCES BE LAID IN STANDING WATER. CONDUCT THE DISCHARGE FROM TRENCH DE-WATERING TO DRAINS OR NATURAL DRAINAGE CHANNELS. F. SPECIAL SUPPORTS:
- WHENEVER, IN THE OPINION OF THE ENGINEER, THE SOIL AT OR BELOW THE PIPE GRADE IS UNSUITABLE FOR SUPPORTING SEWERS AND APPURTENANCES SPECIFIED IN THIS SECTION. SUCH SPECIAL SUPPORT. IN ADDITION TO THOSE SHOWN OR SPECIFIED, SHALL BE PROVIDED AS THE ENGINEER MAY DIRECT, AND THE CONTRACT WILL BE ADJUSTED.
- BACKFILL SHALL BE PLACED AS SHOWN IN THE PLANS. COMPACT THIS BACKFILL THOROUGHLY, TAKING CARE NOT TO DISTURB THE PIPE. BACKFILL UNDER AND WITHIN 5 FEET OF WALKS, PARKING ARFAS, DRIVFWAYS AND STREETS SHALL BE GRANULAR MATERIAL ONLY AND THOROUGHLY COMPACTED BY APPROVED METHODS.
- H. PLASTIC SEWER PIPE INSTALLATION: PLASTIC SEWER PIPE SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321 PER LATEST REVISION. PIPES SHALL BE TESTED AFTER THIRTY DAYS, USING A MANDREL THAT IS 95% OF THE INSIDE DIAMETER OF THE PIPE BEING TESTED. SAID MANDREL SHALL BE PULLED BY HAND THROUGH EACH PIPE SECTION TO ENSURE DEFLECTION IS LESS THAN ACCEPTABLE LIMITS.
- STORM WATER CONNECTIONS NO ROOF DRAINS, FOOTING DRAINS AND/OR SURFACE WATER DRAINS MAY BE CONNECTED TO THE SANITARY SEWER SYSTEMS, INCLUDING TEMPORARY CONNECTIONS DURING CONSTRUCTION.
- WATERLINE CROSSING: WHERE WATER LINES AND SANITARY SEWERS CROSS AND WATER LINES CANNOT BE PLACED ABOVE THE SEWER WITH A MINIMUM OF 18 INCHES VERTICAL CLEARANCE, THE SEWER MUST BE CONSTRUCTED OF WATER WORKS GRADE DUCTILE IRON PIPE WITH MECHANICAL JOINTS WITHIN 10 FEET OF THE WATER LINE.

INDIVIDUAL BUILDING LINES SHALL BE 6 INCHES IN DIAMETER AND OF MATERIAL EQUAL TO THAT SPECIFIED IN

2A OF THIS SECTION. SERVICE LINES SHALL BE CONNECTED TO THE MAIN SEWER AT LOCATIONS SHOWN IN

K. UTILITIES: IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERITY ALL EXISTING UTILITIES AND CONDITIONS PERTAINING TO HIS WORK. IT SHALL ALSO BE THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE OWNERS OF THE VARIOUS UTILITIES BEFORE WORK IS STARTED. THE CONTRACTOR SHALL NOTIFY IN WRITING THE OWNER AND THE ENGINEER OF ANY CHANGES, ERRORS OR OMISSIONS FOUND ON THESE PLANS OR IN THE FIELD BEFORE WORK IS STARTED OR RESUMED.





2 8 7 9 2 4 N 2 -

